



Mu2e Facility

Master Planning Meeting

4/4/11


R. Ray Mu2e Project manager

Mu2e Site




R. Ray - Mu2e WGM


Surface Building




Grade Level



Detector Enclosure




Rails




R. Ray - Mu2e WGM

Connection to Pbar



External Beamline



R. Ray - Mu2e WGM








R. Ray - Mu2e WGM

MI-52 Site Plan



MI-52 Extension



Site Utilities

Roads and Hardstands

- 800LF of removed Kautz Road
- 1400LF of new Kautz Road
- 350 LF of new Well Pond Road
- 350LF of new Access Road
- 15,000SF of Parking and Hardstand

Piped Utilities

- 1,085 LF DWS
- 525 LF Sanitary Sewer
- 1085 LF 10" ICW
- 550 LF 6" ICW
- 1370 LF Chilled Water S&R

Electrical Power

- Three feeders from MSS:
- 16,700 new 15KV cable
- 5 new configuration switches
- 6 new -1500KVA Transformers
- Electrical / Comm. Duct Bank
 1250 LF

Environmental


- Flood Plain and Wetland delineation is complete.
- The project will disturb low grade wetlands.
- Pursuing Wetland Assessment to apply for CX Determination.
- Corp of Engineer "Wetland" permit has been initiated

Sustainability


- Pursuing DOE Exemption LEED Gold Certification
- Will Comply with Guiding Principles.

Backup Slides

Why does the building have to go in the middle of a road?



Some sites we have evaluated




Constraints

There are several factors that come into play when considering the location of Mu2e:

- Where can we connect to the Debuncher Ring?
- Beam requirements for the AC Dipole
- Wetlands and Indian Creek.


Debuncher Connection

- There is only one good location for connecting to the Debuncher Ring.
 - An existing beamline from the Booster connects to the pbar source at this location, so a stub allowing easy connection to the Debuncher with minimal demolition already exists.
- AD/PBAR experts who have walked the tunnel tell us that connecting anywhere else is extremely difficult and costly.
 - Other locations require significant demolition, relocation of A/D line, significant splicing and relocation of cables, power busses, etc.




Length of beamline

- An AC dipole, located in the external beamline, is required to extinguish beam between pulses that can cause background.
- Significant optics is required to properly prepare the beam for the AC dipole.
 - Large betatron function in the bend plane
- This is very advanced optics.
 Not a simple transfer line.
- Also not a gold plated beam line.
 We don't cancel the derivative of the dispersion at the target, something we would do if we had more space.



Current Location

- We were able to squeeze some space out of the upstream bends. Can't gain anymore without reducing β_x.
- Reducing β_x increases the cost and technical risk associated with the AC dipole.
- The current location minimizes the cost and the project risk.
 Any other location will increase the cost.



Precedent for diversion of Kautz Road

